

UNIVERSITY OF HYDERABAD
ENGINEERING DEPARTMENT

Office of the Assistant Engineer

NOTE

Ref: UH/ENGG/UE/2026-27/

Date: 21.07.2026.

The **Opening of Quotations (Below Rs. 50,000/-)** for the works mentioned below is scheduled to be held on **24.07.2026 at 12.00 P.M. in the Office of the University Works Department.** Hence, All the contractors are requested to remind the following details: -

Submission of Quotations: 24.07.2026 at 12.00 PM

Opening of Quotations: 24.07.2026 at 3.00 PM

S. No	Name of the work	Estimated Cost Rs.
1	Supply and Fixing of Electrical wiring with Switch boxes and Wall-Mounted fans in Room No-W10, School of Chemistry in University of Hyderabad campus-Reg..	Rs.41,106/-

Sd/-
Assistant Engineer (E)

Name of Work:-Supply and Fixing of Electrical wiring with Switch boxes and Wall-Mounted fans in Room No-W10, School of Chemistry in University of Hyderabad campus-Reg.						
SCHEDULE OF QUANTITIES						
S. No	DSR/MR	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1	1.24	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.				
1.1	1.24.1	5/6 A switch	4	Each	Figure:Rs _____ Words:Rupees _____	
1.2	1.24.3	15/16 A switch	12	Each	Figure:Rs _____ Words:Rupees _____	
1.3	1.24.4	3 pin 5/6 A socket outlet	4	Each	Figure:Rs _____ Words:Rupees _____	
1.4	1.24.5	6 pin 15/16 A socket outlet	12	Each	Figure:Rs _____ Words:Rupees _____	
2	1.27	Supplying and fixing following size/ modules, GI box along with modular base & cover plate for modular switches in recess etc. as required.				
2.1	1.27.2	3 Module (100mmX75mm)	4	Each	Figure:Rs _____ Words:Rupees _____	
2.2	1.27.4	6 Module (200mmX75mm)	6	Each	Figure:Rs _____ Words:Rupees _____	
3	2.1	Supplying and fixing 5 A to 32 A rating, 240/415 V, 10kA, "C" curve, miniature circuit breaker suitable for inductive load of following poles in the existing MCB DB complete with connections, testing and commissioning etc. as required.				
3.1	2.10.1	Single pole	6	Each	Figure:Rs _____ Words:Rupees _____	
3.4	2.10.4	Double pole	1	Each	Figure:Rs _____ Words:Rupees _____	
4	1.14	Wiring for circuit/ submain wiring along with earth wirewith the following sizes of FRLS/HFFR PVC insulated copper conductor, single core cable in surface/recessed medium class PVC conduit as required.				
4.1	1.14.1	2 X 1.5 sq. mm + 1 X 1.5 sq. mm earth wire	4	Meter	Figure:Rs _____ Words:Rupees _____	
4.2	1.14.3	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	36	Meter	Figure:Rs _____ Words:Rupees _____	

5	MR	Supply and fixing of 400mm High Speed Torpedo wall mount fan with 2 Years Warranty Make:- Crompton/Orient/Havels	4	Each	Figure:Rs _____ Words:Rupees _____	
Sub Total						
Add GST@18%						
Total						
1) The estimate amount is inclusive of GST.						
2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.						
Signature of the Contractor			Assistant Engineer			

Terms & Conditions:

1. The contractor/ bidder shall be a registered contractor and should produce definite proof of appropriate class registered by state or central government departments or state/central autonomous bodies or undertakings should submit proof thereof.
2. The work should be completed within Twenty-one (21) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the
3. The contractor should abide by the Labor Laws, Minimum Wages Act & Workmen's Compensation Act.
4. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
5. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
6. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
7. If water is supplied by the University 1% of the actual cost of water consuming items will be recovered from the bills for work done.
8. Seignories charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
9. Defect liability period 6 (six) months from the date of completion of the work.
10. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
11. A.E (E) has to enclose the work completion certificate and user department certificate along with the bill.
12. No quotation will be accepted without PAN/VAT no.
13. TDS (1% or 2%) / Labor welfare cess (1%) will be levied wherever applicable.

Assistant Engineer