

Name of work :- Maintenance of Buildings- "Replacement of Damaged Main entrance Doors of Mens Hostel -F & G " in UoH Campus.

- 1) The estimate amount is inclusive of GST.**
- 2) Comparative statement for Quoted rates shall be based on rates inclusive of GST.**
- 3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them.**
- 4) The HSN Code for each item should be indicated.**

SCHEDULE OF QUANTITIES

S.No	D.S.R.No.	Description of item	Qty	Unit	Rate in figures & Rate in words	Amount
1						
1	1/21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / paneling, C.P. brass/ stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, paneling and dash fasteners to be paid for separately) :	30.00	kg	Figure: Rs _____ Words: Rupees _____ _____	
	A/21.1.1	For fixed portion				
	21.1.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)				
2	2/21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately).			Figure: Rs _____ Words: Rupees _____ _____	
	21.1.2.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)				

			30.00	kg		
3	3/21.3	Providing and fixing glazing in aluminium door, window, ventilator shutters and partitions etc. with EPDM rubber / neoprene gasket etc. complete as per the architectural drawings and the directions of engineer-in-charge . (Cost of aluminium snap beading shall be paid in basic item):	9.24	Sqm	Figure: Rs _____ Words: Rupees _____ _____	
	21.3.1	With float glass panes of 4.0 mm thickness (weight not less than 10 kg/sqm)				
					Total Amount in figures Rs	
		Less Rebate Offered if any _____ Net Amount (excluding GST) _____ Net Amount in words _____ Add GST _____ Total Amount (Including GST) _____ Total Amount in words _____				
1) The estimate amount is inclusive of GST. 2) Comparative statement for Quoted rates shall be based on rates inclusive of GST. 3) The Bidder should intimate GST percentage separately. The GST shall be reimbursed on submission of proof by them. 4) The HSN Code for each item should be indicated.						
Signature of the Contractor Executive Engineer						

Terms & Conditions:

1. The work should be completed within Seven (7) days from the date of issue of work order. Failure to complete the work within the stipulated time will entail recovery of compensation from work bills as decided by the University Engineer.
2. The contractor should abide by the Labour Laws, Minimum Wages Act & Workmen's Compensation Act.
3. This work order can be cancelled and the work stopped at any time by the Officer-in-charge of the work or by any Officer superior to him in authority.
4. The contractor shall permit the University at the time of making intermediate payment(s) to deduct 10% of the value of the work billed for towards Security Deposit. The deposit is liable to be forfeited for non-rectification of defects pointed out to him during the execution of the work/Defect Liability Period.
5. The work shall be done as per CPWD specifications and as directed by the University Engineer from time to time.
6. If water is supplied by the University 1 % of the actual cost of water consuming items will be recovered from the bills for work done.
7. Seignorage charges will be deducted from the bill as per the stipulated rates communicated by the Govt. from time to time.
8. Defect liability period (6) months from the date of completion of the work.
9. For delay or slow progress of work the relevant clauses of CPWD manual will be invoked and penalty levied.
10. No quotation will be accepted without PAN/GST no.
11. GST(2%)/TDS (1% or 2%) / Labour welfare cess (1%) will be levied wherever applicable.

Executive Engineer

CC to:

1. Executive Engineer
1. A.E. Sub-Division (C-)
2. S O (Works & Bills),
3. Finance & Account
4. O.C.,
5. D.B.,